

# How the Last Planner System is used in Target Value Delivery

**Glenn Ballard**

## Introduction

Target Value Delivery (TVD) and the Last Planner System (LPS) are two of the primary tools used in Lean Construction. Understanding how they work together is needed to use both properly. The Last Planner System began its life in 1991 as a system for planning and control of production on projects. The 2020 Current Process Benchmark describes the Last Planner System's current form, which is to be the planning and control process for both project and production. Target Value Delivery is a process for setting project value and cost targets prior to design, then steering design and construction to those targets. TVD was adapted from Toyota's product development process in 2002, but its roots are deeper, extending at least as far back as Henry Ford in the 1910s. A book titled "Target Value Delivery of Building Projects" (Ballard and Morris, 2023) scheduled for publication by the end of 2023, will do the same for Target Value Delivery. The book reports on research that began in 2016 by the Project Production Systems Laboratory at the University of California Berkeley. This research found that TVD is better than traditional forms of project delivery and its functions and methods can be learned and used by everyone. This is supported by the TVD book with descriptions how clients, cost management consultants, architectural/engineering companies, and general contractors use TVD.

I will first describe how targets are set in TVD, then outline how steering is done, followed by examining the role LPS plays.

## How Value/Cost Targets are set in TVD

### Presuppositions

1. A first presupposition (initial assumption) of TVD is that project target value can be set prior to design, based on the objectives for the project. Value targets are needed for achieving those objectives.
2. A second key presupposition is that an allowable cost can be set based on expected benefits from hitting value targets.
3. A third key presupposition is that cost can be set for achieving value targets by regressing from the functional program to a facilities program capable of delivering desired functionalities within constraints, then costing that facilities program to produce a probable estimate of cost (expected cost).

Table 1 and 2 are from the TVD book. They describe the functional program and the facilities program for a project.

Functional Program	Description
• <b>Functional Outcomes</b>	Quantitative performance statements: for example, number of procedures to be performed, students to be taught, maximum response time (for buildings such as fire stations), gross operating margin.
• <b>Qualitative Requirements</b>	Adjectival quality statements for example: grand, economical, top of the line Success measures: 100% up-time, meets needs 80% of the time, achieves LEED gold
• <b>External Conditions</b>	Factors external to the program for example: site conditions, existing building conditions (renovation) overall remoteness, availability of skilled labor.
• <b>Irreducible Uncertainty</b>	Uncertainty within the program requirements, for example: quantitative uncertainty, long range outcome changes. Also includes unresolved uncertainty.

**Table 1:** Functional Program (Ballard and Morris, 2023)

Functions to be performed and qualitative characteristics of the building are drawn from the client answering the question "what's wanted?" External conditions and uncertainties must be identified and managed to deliver desired functionalities and capacities.

Facility Program	Description
• <b>Spatial Program</b>	Quantitative measure of number, type, and size of assignable (function) rooms, allowance for non-assignable spaces (corridors, restrooms, elevators, etc.), allowance for structural area.
• <b>Qualitative Requirements</b>	Space performance narrative, measurable requirements (acoustics, lighting, etc.) and qualitative statements. Often referred to as a third key presupposition is that cost can be set for achieving value targets by regressing from the functional program to a facilities program capable of delivering desired functionalities within constraints, then costing that facilities program.
• <b>External Conditions</b>	Impact of external conditions, such as anticipated foundation design, site grading, material selection.
• <b>Irreducible Uncertainty</b>	Uncertainty within the facility requirements, for example, quantitative uncertainty in un-assignable area, space utilization, extent of daylighting access, floor plate efficiency.

**Table 2:** Facility Program (Ballard and Morris, 2023)

Moving from the functional program to the facilities program is done by regressive thinking; i.e., looking for what provides the desired functions. Regressive thinking proceeds by finding and assessing currently known design solutions, using simulation and/or benchmarking. When none of these solutions are fit for purpose, designers must create new solutions using abduction (creative thinking). The simulation tool developed by Finland's Haahtela Group in their use of TVD is described in the TVD book in this way: "What's wanted (target values) and the cost of providing what's wanted (target cost) are determined prior to design by creating through simulation, a model of the building from the voice of the customer; then costing the materials, components and services needed

to construct that building. The simulation model is fully detailed, buildable, and capable of supporting desired functions at desired capacities, but is not what will be constructed, leaving designers free to create designs that deliver target values within the target cost.”

**How Projects are Steered to Value/Cost Targets**

“In TVD current best practice, once targets are set, multiple alternatives for building systems and components are generated using **Set-Based Design**, then evaluated against factors relevant for differentiating them using **Choosing by Advantages**. The total importance of advantages of each are determined (the benefits they offer), then evaluated against their cost. If none of the alternatives is found to deliver their part of target value, design’s job is not yet done, regardless of cost. If target values are achieved, but at greater than target cost, designers continue striving for ways to achieve target values at lower cost using **Value Engineering Methods**” (From TVD in Building Projects)

To the three methods in **bold** in the above paragraph must be added a fourth: how design is organized on TVD projects. Table 3 and Table 4 were provided by the Boldt Companies. It shows the Leaders, Members, Coaches and Estimators in Innovation Teams for Site/Civil, Shell & Core, Fit Out, etc. Individuals are color-coded by company. It is apparent that the teams are multi-functional and include trade partners (specialty contractors-color coded black).

- 3. Site/Civils assumed soil conditions were known and did not allow time for testing.
- 4. Same as # 1 above.
- 5. Confusion over who had what responsibility.

All five failures were the result of not understanding something critically important-as opposed to mistakes in calculation or otherwise within the design act. The fundamental causes of non-completion were failure to follow two LPS processes: the reliable promising process and learning from experience.

How well do TVD projects perform using LPS, Innovation Teams, Set-Based Design, Choosing by Advantages and Value Engineering methods?

Table 5 reports the cost savings achieved on a complex multi-year program for designing and delivering various types of out-patient facilities for Advocate Aurora Health in the United States. Here are the measured cost savings: 2016-0.5%, 2017-9.2%, 2018-18.9%, 2019-14.5%. Estimated cost savings for 2020 and 2021 were forecast and later confirmed at 16% and 18%. These savings are for the entire program. More important over time is the cumulative effect of adjusting cost standards annually for each building type in the program. In addition, there were improvements in fitness for purpose and speed of delivery. A more detailed report is included

	Site & Civil	Shell & Core	Fit Out	MEP/IT	MARX Elev & Technology Hardware	Technology Teams	Production / BIM	Communications	Contractors/Design	Trade Partners
<b>Leader</b>	David Blumenthal	Brian Bassett	John Buchanell	Tom D'Andrea	Andy Lewis	Bob Papp	Pete Salvo (Production) Graham Ryan (BIM)	Daniel Peruchbacher	Graham Ryan	Angel Ortiz
<b>Co-Lead</b>	Brian Bassett	Brian Fry	Marya Goff	Bob Papp	Terry Hender (Equip)	Mike Neely	Angel Ortiz	Nick Loughrin	Angela Ortiz	Pete Salvo
<b>Coach</b>	Nick Loughrin	Daniel Peruchbacher	Daniel Peruchbacher	Daniel Peruchbacher	Nick Loughrin	Nick Loughrin	Nick Loughrin	Daniel Peruchbacher	Nick Loughrin	
<b>Team Members</b>	Darren Maas Dylan Fry Tom D'Andrea Bob Scarpasnik Angela Ortiz Mike Neely Jake Hough Matt Wade Carley Anasta Future Trade Partners	Graham Ryan Angel Ortiz Carley Anasta Graham Ryan Brian Johnson Nik Scarpasnik Brynn Fry Mike Neely Tom D'Andrea Carley Anasta Future Trade Partners	Marya Goff Carley Anasta Graham Ryan Tom D'Andrea Brittany Hanson Bob Papp Tim Kehoe Adrienne Carlson CHW IT Help Todd Olsen Pawel Makal Adrienne Carlson Nate Wheeler Mike Schickel (Electrical) Jim Sorbuck (MEP/C) Kas Berghede Pawel Makal Joe Lambert	Tom D'Andrea Brittany Hanson Bob Papp Tim Kehoe Adrienne Carlson CHW IT Help Todd Olsen Pawel Makal Adrienne Carlson Nate Wheeler Mike Schickel (Electrical) Jim Sorbuck (MEP/C) Kas Berghede Pawel Makal Joe Lambert	Andy Lewis Terry Hender (Equip) Mike Neely Bob Papp Tom D'Andrea Brittany Hanson Nate Wheeler Adrienne Carlson	Bob Papp Tom D'Andrea Brittany Hanson Nate Wheeler Mike Schickel (Electrical) Jim Sorbuck (MEP/C) Kas Berghede Pawel Makal Joe Lambert	Bob Papp Tom D'Andrea Brittany Hanson Nate Wheeler Mike Schickel (Electrical) Jim Sorbuck (MEP/C) Kas Berghede Pawel Makal Joe Lambert	Pete Salvo (Production) Graham Ryan (BIM) Angel Ortiz Nick Loughrin Sam Green Jackie Ganger Brian Bassett Ethan Morrison Daniel Peruchbacher Brynn Fry Tom D'Andrea Carley Anasta Future Trade Partners	Graham Ryan Angela Ortiz Nick Loughrin Sam Green Jackie Ganger Brian Bassett Ethan Morrison Daniel Peruchbacher Brynn Fry Tom D'Andrea Carley Anasta Future Trade Partners	Angel Ortiz Pete Salvo Nick Wade Steve Johnson Ethan Morrison Daniel Peruchbacher Brynn Fry Tom D'Andrea Carley Anasta Future Trade Partners
<b>Target Value Estimator</b>	Chris P.	Chris P.	Chris P.	Bob P.	Andy Lewis	Bob P.	Chris P.	N/A	N/A	N/A
<b>KEY</b>	CHW	Canon	Boldt	Ag & B	Opal	Zimmerman	Trade Partner			

**Table 3:** Innovation Teams (courtesy of the Boldt Companies)

The Innovation Teams apply LPS—they participate in pull planning sessions to create phase schedules, they do lookahead planning to make scheduled tasks ready to be performed, they commit to 2-week work plans and when a committed task is not completed as planned, they search for countermeasures and test them at the next instance of that task. A template for LPS use by Innovation Teams (color-coded) is shown below.

To better understand the importance of LPS to TVD, here is a true story from a 7000 seat, fully enclosed amphitheater, courtesy of Linbeck Construction. The project averaged 61% PPC (percent plan complete) during its design phase. The Site/Civils team was best at 78% PPC so I asked them to select five of their plan failures and analyze them using 5 Whys. Here’s what they found:

- 1. Site/Civils assumed City requirements for traffic analysis were the same as before.
- 2. MEP (mechanical, electrical, plumbing) did not understand Site/Civil's requirements for drainage, resulting in a Site/Civils plan failure.

in Ballard and Morris (2023).

**What does LPS do to support TVD?**

Apart from the functions performed in Project Definition, all remaining LPS functions are performed in Target Value Delivery, both in design and in construction:

- Pull planning is used to detail generation and selection from alternatives for the design of building systems and each sub-phase of design and construction.
- Lookahead planning is used to make scheduled tasks ready to be executed, through constraints removal and collaborative design of work methods (virtual prototyping, physical prototyping, first run studies).
- Commitments are made through the reliable promising process.
- Broken promises are analyzed to find and test countermeasures.
- Participation in LPS planning and learning helps create the culture of intense collaboration needed to support innovation and continuous improvement.

CHW MCIP 2-week Planning Cycle

WEEK A						Outcomes of the Week:	
Monday	Tuesday Colocated at Summit	Wednesday Colocated at Summit	Thursday	Friday			
	VDC/BIM Check-in Final Design Review Final Lookahead Plan Risk Working Brown Design Update	Interiors Coordination Meeting			Brown Package - PPC For Last Week Updated - Lookahead Plan Updated - Additional Pull Plans Performed - Design Progress Communicated - Next Week's Plan Committed to	Black Package - PPC For Last Week Updated - Lookahead Plan Updated - Additional Pull Plans Performed - Design Progress Communicated - Next Week's Plan Committed to	
	Brown Lookahead Plan Brown Working				Blue Package - PPC For Last Week Updated - Lookahead Plan Updated - Additional Pull Plans Performed - Next Week's Plan Committed to - User Group / WOW Schedule, Design Options & Cost Impacts Aligned	Red Package - PPC For Last Week Updated - Next Week's Plan Committed to - New Major Constraints Identified	
	Blue Revit Review Blue WOW/UG Planning Blue Lookahead Plan				Purple Package - PPC For Last Week Updated - Lookahead Plan Updated - Additional Pull Plans Performed - Design Progress Communicated - Next Week's Plan Committed to - User Group / WOW Schedule, Design Options & Cost Impacts Aligned	Green Package - PPC For Last Week Updated - Next Week's Plan Committed to - New Major Constraints Identified	
Connected Decisions / Check PPC	Purple Design Update Purple WOW/UG Planning Purple Lookahead Plan	Project Information and Commit to Next Week's Schedule Big Room Plus/Delta and Agenda	Bergers Estimates Sent ESPC Estimates Sent Revit Pictures of Booth			Orange Package - PPC For Last Week Updated - Next Week's Plan Committed to - New Major Constraints Identified	

  

WEEK B						Outcomes of the Week:	
Monday	Tuesday Colocated at Summit	Wednesday Colocated at Summit	Thursday	Friday			
	VDC/BIM Check-in Red Revit Review Red WOW/UG Planning Red Lookahead Plan	Interiors Coordination Meeting			Brown Package - PPC For Last Week Updated - Next Week's Plan Committed to - New Major Constraints Identified	Red Package - PPC For Last Week Updated - Lookahead Plan Updated - Additional Pull Plans Performed - Revit Updates Communicated - Next Week's Plan Committed to - User Group / WOW Schedule, Design Options & Cost Impacts Aligned	
	Green Design Update Green WOW/UG Planning Green Lookahead Plan				Blue Package - PPC For Last Week Updated - Next Week's Plan Committed to - New Major Constraints Identified	Green Package - PPC For Last Week Updated - Lookahead Plan Updated - Additional Pull Plans Performed - Revit Updates Communicated - Next Week's Plan Committed to - User Group / WOW Schedule, Design Options & Cost Impacts Aligned	
Connected Decisions / Check PPC	Orange Design Update Orange WOW/UG Planning Orange Lookahead Plan	Project Information and Commit to Next Week's Schedule Big Room Plus/Delta and Agenda	Connector Estimates Sent Generator Estimates Sent Revit Pictures of Booth		Orange Package - PPC For Last Week Updated - Lookahead Plan Updated - Additional Pull Plans Performed - Revit Updates Communicated - Next Week's Plan Committed to - User Group / WOW Schedule, Design Options & Cost Impacts Aligned	Black Package - PPC For Last Week Updated - Next Week's Plan Committed to - New Major Constraints Identified	

Table 4: Template for Innovation Teams use of LPS (courtesy of the Boldt Companies)

AAOC Program Statistics Normalization Summary		Baseline Project Comparables			Year RESULTS		
Project Name	Year/Date	Project Type	Project Date	Project Cost \$/SF	Project Name	Year	% Savings
		A-Ground Up	6/20/2016	\$335	Candell (cost)	2016	0.5%
		A-Ground Up	6/20/2016	\$344	Candell (model)	2017	9.2%
		B-White Box TI	4/18/2017	\$316	North Broadway (cost)	2018	18.9%
		D-White Box TI		TBD	North Broadway (model)	2019	14.5%
		C-MOB TI	4/18/2017	\$316	North Broadway (cost)	2020	16.0%
		D-Renovations		TBD	TBD	2021	18.0%
		E-Other		TBD	TBD		
		F-Small/One-Off		TBD	TBD		

Summary of RESULTS: All Projects							Summary of PROGRESS: All Projects						
Project Name	Project Year/Date	% Savings to Comparable	Project Type	Normalized \$/SF	Comparison \$/SF	Comparison Project	Project Name	Project Year/Date	% Savings to Comparable	Project Type	Normalized \$/SF	Comparison \$/SF	Comparison Project
Candell	Jun-14	2.7%	A-Ground Up	\$335	\$335	Candell (Model)	Burbank (Budget)	Feb-20	-12.1%	B-White Box TI	\$335	\$335	North Broadway (cost)
Sequoia	Jun-16	-1.8%	A-Ground Up	\$335	\$330	Candell (Model)	Burbank (Current)	Mar-21	16.0%	B-White Box TI	\$323	\$338	North Broadway (cost)
Huntley	Jul-17	4.0%	A-Ground Up	\$335	\$362	Candell (Model)	Burbank (Target)	Mar-21	20.1%	B-White Box TI	\$266	\$338	North Broadway (cost)
Good Lam Growth							(Budget)	Mar-22	10.3%	B-White Box TI	\$277	\$268	North Broadway (cost)
Deer Plains	Aug-17	11.0%	A-Ground Up	\$335	\$322	Candell (Model)	Lake Villa (Target)	May-21	37.2%	A-Ground Up	\$109	\$105	Candell (Model)
Cell Linn	Mar-19	13.1%	A-Ground Up	\$335	\$339	Candell (Model)	Lake Villa (Budget)	May-21	16.2%	A-Ground Up	\$310	\$318	Candell (Model)
Murder in	Nov-18	3.8%	B-White Box TI	\$280	\$313	North Broadway (cost)	Naperville (Budget)	Dec-20	16.1%	B-White Box TI	\$321	\$338	North Broadway (cost)
South Moland	Mar-17	0.0%	B-White Box TI	\$312	\$312	North Broadway (cost)	Naperville (Current)	Feb-21	15.1%	B-White Box TI	\$302	\$337	North Broadway (cost)
Lombard	Jan-18	12.2%	B-White Box TI	\$283	\$322	North Broadway (cost)	Naperville (Target)	Feb-21	20.1%	B-White Box TI	\$235	\$287	North Broadway (cost)
Sifco	Jun-18	22.0%	B-White Box TI	\$247	\$295	North Broadway (cost)	Park Ridge (Budget)	Apr-22	2.8%	B-White Box TI	\$300	\$300	North Broadway (cost)
Imani Village	Dec-18	17.2%	B-White Box TI	\$283	\$334	North Broadway (cost)	Park Ridge (Retrofit)	Mar-22	21.4%	B-White Box TI	\$235	\$332	North Broadway (cost)
West Dundee	Feb-19	17.1%	B-White Box TI	\$278	\$335	North Broadway (cost)	Dreyer Reservoir 35.8k (Budget)	Mar-22	21.0%	B-White Box TI	\$232	\$300	North Broadway (cost)
Lake View	Jul-18	16.7%	B-White Box TI	\$277	\$330	North Broadway (cost)	Dreyer Reservoir 35.8k (Target)	Apr-22	21.0%	B-White Box TI	\$232	\$332	North Broadway (cost)
South Deerfield	Sep-15	1.8%	C-MOB TI	\$305	\$305	North Broadway (cost)	Dreier Reservoir 35.8k (Target: 30,420 & 4,380 Cost)	Feb-22	21.0%	B-White Box TI	\$232	\$332	North Broadway (cost)
Orwell Lake	Sep-17	16.5%	C-MOB TI	\$305	\$305	North Broadway (cost)	Six Corners TI (Budget)	Feb-21	12.0%	B-White Box TI	\$312	\$337	North Broadway (cost)
Randsall Road	Oct-18	3.5%	C-MOB TI	\$314	\$332	North Broadway (cost)	Six Corners TI (17,890 SF Target)	May-22	22.0%	B-White Box TI	\$268	\$308	North Broadway (cost)
Living & Western	Feb-19	20.3%	C-MOB TI	\$305	\$336	North Broadway (cost)	South River (Budget)	Apr-22	10.1%	C-MOB TI	\$334	\$332	North Broadway (cost)
Delaware Addition	Mar-20		A-Ground Up	\$435	\$435	Candell (Model)	Algonquin (Budget)	Mar-22	11.5%	C-MOB TI	\$320	\$359	North Broadway (cost)
Del Flint Addition	Apr-20		A-Ground Up	\$415	\$388	Candell (Model)	1500 sq-ft (Budget)	May-22	-8.1%	C-MOB TI	\$424	\$369	North Broadway (cost)
Hopkinton	Jul-20		B-White Box TI	\$255	\$320	North Broadway (cost)	Batavia Addition (Target)	Jan-22	4.3%	B-White Box TI	\$312	\$330	North Broadway (cost)

Table 5: Cost Savings over 5 years (courtesy of HDR Architecture & Engineering)

References

Ballard, G. and Morris, P. 2023. Target Value Delivery of Building Projects. Cambridge Scholars Publishing. Publication Pending. Ballard,

G. and Tommelein, I.T. 2021. 2020 Current Process Benchmark for the Last Planner System of Project Planning and Control. Lean Construction Journal.